PROJECT: EXTERIOR STUCCO PAINT CENTRAL OFFICE 19-018-9999

WORK INCLUDED

- A. Pressure wash all areas to be painted.
- B. Prepare existing stucco for new paint.
- C. Patch any holes, cracks, crumbling or peeling areas or other damage prior to painting with syucco material to match existing surface.
- D. Apply 2 coats of masonry paint to all areas of stucco and trim or flashing if applicable.
- E. Paint to be commercial grade exterior masonry paint. Color to be chosen by THA representative.
- F. All materials are to be removed from site daily and work area is to be kept clean and in a workable environment.
- G. Reasonable caution will be made to ensure there is no overspray on surrounding cars, brick, sidewalk or other areas not being painted.
- H. Contractor will be responsible for cleaning any areas affected by over spray.

SECTION 09900 PAINTING

2.01 ACCEPTABLE MANUFACTURERS

A. Coronado D. Kelly-Moore G. Anchor

B. PPG E. Porter H. Pratt and Lambert

C. Sherwin Williams F. Sonneborn

I. Acceptable manufacturer's shall be as referenced above or approved equal. Deliver paint materials in sealed original labeled containers, bearing manufacturer's name, type of paint, color designation and instructions of mixing and/or reducing.

2.02 APPLICATION EQUIPMENT

- A. All necessary equipment shall conform to OSHA regulations and local ordinances.
- B. General: For application of the approved paint, use only such equipment as is recommended for application of the particular paint by the manufacturer of that paint, subject to the approval of the Housing Authority.
- C. Compatibility: Prior to actual use of application equipment, use all means necessary to verify that the proposed equipment is actually compatible with the material to be applied and that the integrity of the finish will not be jeopardized by use of the proposed application equipment.

PART 3 EXECUTION

3.00 INSTALATION

- A. Thoroughly examine surfaces scheduled to be painted prior to commencement of work. Do not commence until such defects have been corrected.
- B. Correct defects and deficiencies in surfaces, which may adversely affect work of this Section.

3.01 TESTING

A. The Contractor, at no cost to Owner, shall correct any work that does not conform to the manufacturer's specification requirements.

3.02 PROTECTION

- A. Adequately protect other surfaces from paint and damage.
- B. Furnish sufficient drop cloths, shields, and protective equipment to prevent spray or droppings from fouling surfaces not being painted and in particular, surfaces within storage and preparation area.

- Place cotton waste cloths and material which may constitute a fire hazard in closed metal containers and remove daily from site.
- D. Remove electrical fixtures, surface hardware, fittings, and fasteners, prior to painting operations. These items are to be carefully stored, cleaned, and replaced on completion of work in each area. Do not use solvent to clean hardware that may remove permanent lacquer finish.
- E. Barricade work area to prevent pedestrian traffic. Contractor shall erect temporary interior signs to direct traffic to alternate means of ingress and egress when ever points of entry are blocked.
- F. Secure scaffolding and lines at a height sufficient to prevent vandalism and mischief at close of work each day.
- A. Examine all surfaces on site to determine job conditions and degree of surface preparation necessary for a professional job.
- B. Perform all preparation and cleaning procedures in strict accordance with the paint manufacturer's recommendations as approved by the Housing Authority.

3.03 APPLICATION

- A. Mix and prepare painting materials in strict accordance with the manufacturer's recommendations as approved by the Housing Authority.
- B Stirring: Stir all materials before application to produce a mixture of uniform density, and as required during the application of materials. Do no stir into the material any film which may form on the surface. Remove the film and, if necessary, strain the material before using.
- C. Remove all removable items which are in place and are not scheduled to receive paint finish or provide surface applied protection prior to surface preparation and painting operations.
- D. Following completion of painting in each space or area, reinstall the removed items by using workmen skilled in the necessary trades.
- E. Ensure all materials to be finished are dry, clean and surrounding air temperature is above 45 Degrees Fahrenheit before applying finishes. Provide adequate and continuous ventilation.
- F. Acceptance of Work is subject to the approval of the THA Representative.

3.04 PAINTING AND FINISHING SCHEDULE

- A. Metal Door Frames
 - 1. Primer as recommended.
 - 2. DTM latex, semi-gloss paint. Color to be chosen by THA Job Representative
 - 3. 4.5 mils total dry thickness

3.05 CLEANING

- A. Protect all work at all times. Protect adjacent work and materials by suitably covering or other method during work in progress.
- B. During progress of work keep premises free from any unnecessary accumulations of tools, equipment, surplus materials, and debris.
- C. Thinners or other paint materials shall not be disposed of in the building plumbing system.
- D. Upon completion of work leave premises neat and clean.

3.06 GUARANTEE

Contractor to guarantee work against all defects for a minimum period of one (1) year from the date of final acceptance and make good by repair at no cost to Owner any portion that may show defects in either workmanship or materials during that period.

END OF SECTION

HOUSING AUTHORITY OF THE CITY OF TULSA FORM OF BID

- 1.1 PROJECT: EXTERIOR STUCCO PAINT AT CENTRAL OFFICE (19-018-9999)
- 1.2 LENGTH OF CONTRACT This contract will commence pursuant to the Notice to Proceed. All work and punch list items to be completed by May 26, 2019.
- 1.3 The undersigned, having familiarized themselves with the conditions affecting the cost of the work, the Form of Contract, as prepared by the Housing Authority of the City of Tulsa, 415 E. Independence, Tulsa, Oklahoma 74106, hereby proposes to furnish all Permits, Licenses, Insurance, Labor, Materials, Equipment, Services, Freight, Applicable Taxes and Fees required to perform the duties as per THA Specifications for ITEMS LISTED ABOVE, at the above identified location (s) for the following amount:

1.4	PLEASE ENTER BASE BID	AMOUNT PER	THE SUMMARY	OF WORK
1.7	I LEASE ENTER DASE DID	AMOUNTER	THE BUILDIANT	OF WORK

CITY OF TULSA.

	\$					
	WRITTEN					
	BID ACCEPTANCE OR REJECTION: The Authority reserves the right to accept or reject any or all bids; to waive minor irregulariti or formalities. Price alone will not be the sole determining criteria in awarding of bid.					
M/WBE / SECTION 3 CERTIFICATION						
	A M/WBE is a business in which a this page.)	woman or a minority owns and operates at least 51% of th	e business. (See minority list at bottom			
		e that provides economic opportunities for a class of person number of such persons; or meets such other criteria as the				
	☐ - is a M/WBE	☐ - is <u>not</u> a M/WBE				
	☐ - is Section 3	☐ - is <u>not</u> Section 3				
	COMPANY NAME:					
		CITY:				
	PHONE NUMBER:	FEIN NUMB	BER:			
	E-MAIL:					
	SIGNATURE:DATE:					
	PRINT NAME: TITLE:					
	NAME OF COMPANY OWNER	R:				

MINORITIES: Black American, Native American, Hispanic American, Asian/Pacific American, Hasidic Jew

In submitting this bid, it is understood the right is reserved by the HOUSING AUTHORITY OF THE CITY OF TULSA to reject any and all bids. No bid shall be withdrawn for a period of sixty (60) days subsequent to the opening of bids without the consent of the HOUSING AUTHORITY OF THE